

SECTION 01500

CONSTRUCTION FACILITIES AND TEMPORARY CONTROLS

PART 1 – GENERAL

1.01 SECTION INCLUDES

- A. Regulatory requirements.
- B. Storage
- C. Barriers.
- D. Water control.
- E. Progress cleaning.

1.02 REGULATORY REQUIREMENTS

- A. Comply with applicable laws and regulations of authorities having jurisdiction, including but not limited to building codes, health and safety regulations, utility company regulations, and environmental protection regulations.
- B. Provide electrical equipment which is UL listed.

1.03 STORAGE

- A. Contractor shall provide and pay for storage of materials and equipment off site when on-site storage is not adequate.
- B. Contractor shall transport materials to site(s) as required for performance of Work on a daily basis.

1.04 BARRIERS

- A. Provide barriers to prevent unauthorized entry to construction areas and to protect existing facilities and adjacent properties from damage from construction operations.
- B. Provide protection for plant life designated to remain. Replace damaged plant life.
- C. Protect vehicular traffic, stored Products, site and structures from damage.

1.05 WATER CONTROL

- A. At all times during the construction of Work on this Project maintain the flow of storm water, naturally occurring water and wastewater in existing facilities and channels affected by the Work.
- B. Particular attention is directed to above requirement in regard to the maintenance of flow in existing sewer service connections during removal and replacement of the sewer mains.
- C. Contractor assumes responsibility for damages to property caused by flooding due to blocking or restriction of storm water passages, natural waterways, and wastewater facilities.
- D. Do not at any time permit wastewater flow from existing sewers to flow into nearby waterways or to flow on surface areas.

1.06 PROGRESS CLEANING

- A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.
- B. Remove waste materials, debris, and rubbish from site daily and dispose off-site.
- C. Remove mud and construction debris on a daily basis from paved surfaces used by the Contractor.

PART 2 – PRODUCTS

NOT APPLICABLE TO THIS SECTION

PART 3 – EXECUTION

NOT APPLICABLE TO THIS SECTION

END OF SECTION